

# **Grid Operations and Planning Report**

ERCOT Board of Directors May 20, 2009

**Kent Saathoff** 

#### Content

#### Summary

#### March 2009 Operations

- Peak Demand: Actual vs. Forecast
   On-line Resources: Total at Peak and Wind
- Day-Ahead Load Forecast Performance
- Out of Merit Capacity Order (OOMC) & Replacement Reserve (RPRS)
   Purchases

2

- Zonal Congestion
- Significant System Incidents
- Advisories, Alerts and EECPs
- Other Items

#### Planning Activities

- Summary
- Generation Interconnection Requests
- Wind Capacity




### **Summary**

### March 2009 Operations

- The peak demand of 39,309 MW on March 2<sup>nd</sup> was less than the long term forecast of 41,539 MW for March.
- Day-ahead load forecast error for February was 3.24%.
- Increased instances of zonal transmission congestion in March was due to significant planned transmission outages
- No Advisories, Alerts for Adjusted Responsive Reserve under 2500 MW or EECP events.
- Three transmission alerts
- 243 active generation interconnect requests totaling over 97,000 MW.
   Down from 262 requests with over 105,000 MW in March.
- Executed RMR contract for Luminant Permian 5.
- 8,135 MW wind capacity on line April 30, 2009. Up from 8,065 MW in March.




# Daily Peak Demand: Hourly Average Actual vs Forecast, Resource Plan & On-line Capacity at Peak





Note: All data are hourly averages during the peak load hour obtained from Resource Plans, and EMMS.


# Actual Wind Output w/ Curtailment Added Back Vs Wind Day-Ahead Resource Plan Based on AWS Forecast at Peak Load Hour



<sup>\*</sup> Wind Day-Ahead Resource Plan values based on 80% probability of exceedance forecast




# **Monthly Peak Demand: Actual**





# **Monthly Minimum Demand: Actual**






# Day-Ahead Load Forecast Performance in March 2009

	Mean Absolute Percent Error (MAPE) for ERCOT Mid-Term Load Forecast (MTLF) Run at 16:00 Day Ahead							
	2006 MAPE	2007 MAPE	2008 MAPE	2009 MAPE (YTD)	March 2009 MAPE			
Average Annual MAPE	3.79	3.55	3.30	3.61	3.24			



# Capacity Purchases of RMR, OOMC & RPRS to Manage Local Congestion in March 2009





# **Zonal Congestion**

CSC	Mar 08 Days	Jan 09 Days	Feb 09 Days	March 09 Days	Last 12 Months Total Days (Feb 08 - Feb 09)
North – Houston	4	0	0	<b>9</b> March – 18, 19, 23-25, 27, 29-31	80
North – West	2	0	1	<b>2</b> March – 11, 12	14
West – North	28	19	14	<b>13</b> March – 2- 8, 10, 11, 16-18, 28	197
South – North	9	1	0	<b>3</b> March – 1, 11, 12	33
North - South	13	2	0	<b>7</b> March – 4-9, 18	107



### Significant System Incidents in March 2009

- March 18<sup>th</sup> at 07:14
  - A station breaker failed resulting in two unit trips.
- March 04<sup>th</sup> ,19<sup>th</sup> , and 21<sup>st</sup>
  - Day—ahead Ancillary Service Market did not meet the Market time line.
- March 04<sup>th</sup> and 8<sup>th</sup>
  - The Day-ahead Replacement Reserve Service Market did not meet the Market time line



#### **Advisories and Alerts in March 2009**

- No Advisories issued for Adjusted Responsive Reserve (ARR) below 3000 MW.
- No Alerts issued for ARR below 2500 MW in March 2009.
- Transmission Alerts (operation beyond n-1 criteria):
  - 03/27 04:44 Transmission Alert in Turkey area due to a forced outage in Matador area.
  - 03/27 13:47 Transmission Alert for the loss of Lon Hill Coleto Creek 345KV overloads Warburton - Victoria 138KV
  - 03/28 13:47 Transmission Alert for the loss of Ballinger 138/69KV auto beyond first contingency criteria.
- No EECPs in March 2009




## **Planning Summary**

- ERCOT is currently tracking 243 active generation interconnection requests totaling almost 97,000 MW. This includes over 48,000 MW of wind generation.
- Regional Planning is reviewing proposed transmission improvements with a total estimated cost of \$979.3 million
- All transmission projects (in engineering, routing, licensing and construction) totals approximately \$4.1 billion
- Transmission projects approved in 2009 totaled \$105 million
- Transmission projects energized in 2008 totaled \$453 million
- Executed RMR contract for Luminant Permian 5 through December 31, 2009.




# County Location of Installed Capacity and Interconnection Requests (wind) April 2009






# County Location of Installed Generation and Interconnection Requests (all fuels) April 2009






### **Wind Generation**





(as of April 30, 2009) ERCOT Public

## **Generation Interconnection Activity by Fuel**





ERCOT Public

### Generation Interconnection Activity by Project Phase

