# Bakersfield to Big Hill 345-kV Second Circuit Addition

**RPG Discussion** 

April 6, 2021






#### Introduction


- STEC and LCRA TSC jointly present a Tier 2 RPG project to add a second circuit between Bakersfield and Big Hill 345-kV substations
- The project is the "Stage 1 upgrade" identified in ERCOT's Delaware Basin Load Integration Study
- Proposed project scope:
  - Add 112 miles of new 2-1590 ACSR conductor that matches existing circuit's capacity
  - Upgrade Bakersfield, Big Hill, Cedar Canyon, Noelke, and Schneeman Draw substations to cut-in the new circuit.
- Proposed in-service date: Summer 2023

## Project Map



### **Evaluation of System Needs**

- Implement the improvements identified in the road map for transmission improvements in the Delaware Basin Load Integration study
- Stage 1 upgrades trigger at 3,052 MW load level



Stage	Estimated Delaware Basin Load Level (MW)	Upgrade Element
1	3,052	Add a second circuit on the existing Big Hill – Bakersfield 345-kV line
2	4,022	A new Bearkat – North McCamey – Sand Lake double circuit 345-kV line
3	4,582	A new Riverton – Owl Hills single circuit 345-kV line
4	5,032	Riverton – Sand Lake 138-kV to 345-kV conversion and a new Riverton – Sand Lake 138-kV line
5	5,422	A new Faraday – Lamesa – Clearfork – Riverton double circuit 345- kV line

### **Load Analysis**

- Stage 1 load level (3,052 MW) is surpassed in summer of 2023 in the 2020 U1 SSWG Cases
- TDSPs in the region confirmed load levels on the Delaware Basin busses

Year	MW	MVAR
2022	2915	898
2023	3064	939
2024	3123	956
2024 min	2073	665
2024 HWLL	1906	623

# Analyses

- Stability Analysis:
  - SUM2022 and HWLL2023 Dynamics Working Group (DWG) flat start cases published in April of 2020
  - Contingencies that are a part of McCamey and West Texas Export Generic Transmission Constraints were analyzed
  - The second 345-kV circuit addition is not expected to significantly impact or worsen the system stability in this portion of the system.
- Short circuit Analysis:
  - ERCOT SPWG future 2023 short circuit case
  - The maximum fault duty with the second circuit added is 17 kA (within existing ratings at substations in the region)

## Analyses

- Subsynchronous Resonance (SSR) Analysis:
  - Based on an initial frequency scan performed by ERCOT and the history of the area, it was determined that a detailed SSR study is required for the RPG project.
  - STEC will perform a detailed SSR study and the study results will be submitted to ERCOT as soon as they are available.
  - Scoping and kickoff meeting held on February 11, 2021

### **Project Scope**

#### • STEC will:

- Add roughly 112 miles of new 2-1590 ACSR conductor with a minimum rating of 1,606 MVA.
- The summer normal and emergency ratings of the new second circuit will be the same as the existing circuit.
- Lines will be added on existing right-of-way between Bakersfield and Big Hill substations.
- Obtain CCN to add second circuit.
- STEC's cost estimate is \$49.5M\*.

#### LCRA TSC will:

- Upgrade Bakersfield, Big Hill substations, Cedar Canyon, Noelke and Schneeman Draw substations to accommodate the second circuit addition.
- All substation equipment will have a minimum rating of 4,000 A and 63 kAIC.
- LCRA TSC's cost estimate for the substation work in five substations is \$33.7M\*.

#### Total project cost: \$83.2M\*

\*Latest available estimate prior to final issued design, and subject to revision as additional factors may be identified.

#### Construction Considerations\*

- Begin construction at the east end at Big Hill and work westward toward Bakersfield
- Some construction activities such as foundation installation may take place with the existing circuit energized.
- Some outages will be required to install the davit arms and conductor.

Bakersfield to Big Hill Second Circuit Addition RPG submittal FFB 2021 Regulatory 10 month Design 13 month Procurement 13 months Construct Schneeman Draw to Big Hill 59.1 miles 8 months Construct Noelke to Schneeman Draw 15.8 miles 3 months Construct Cedar Canyon to Noelke 16 miles 3 months Construct Bakersfield to Cedar Canyon 21.1 miles 4 months In Service Date JUN 2023

<sup>\*</sup> Subject to revision as additional analysis is performed and a detailed construction plan is developed.

#### Questions?

#### **Project contacts**

- Doug Evans, STEC
- Sandeep Borkar, LCRA TSC