

San Antonio South Reliability II Project – ERCOT Independent Review (EIR) Status Update

Caleb Holland


RPG Meeting April 9, 2024



- ERCOT provided the study scope and then status updates at the November 2023 and January, February, and March 2024 RPG Meetings
 - <u>https://www.ercot.com/calendar/11142023-RPG-Meeting</u>
 - <u>https://www.ercot.com/calendar/01172024-RPG-Meeting</u>
 - <u>https://www.ercot.com/calendar/02122024-RPG-Meeting</u>
 - <u>https://www.ercot.com/calendar/03182024-RPG-Meeting-_-Webex</u>
- This project is currently under ERCOT Independent Review (EIR)



Recap – Project Need as Seen by ERCOT






3

Recap – Option 10

- Construct a new 345-kV double circuit transmission line from Tango to Marion
- Construct a new 345/138kV switching station on the East side of San Antonio near Beck Rd






Recap – Option 14

- Construct a new 345/138kV switching station on the East side of San Antonio near Beck Rd
- Rebuild the 345-kV single circuit from JK Spruce to Pawnee into a 345-kV double circuit transmission line
- Rebuild the 345-kV single circuit from Pawnee to Tango into a 345-kV double circuit transmission line
- The Spruce to Pawnee 345-kV rebuild and the Pawnee to Tango 345-kV rebuild will be done without the need for extended outages





Comparison of Short-listed Options

| | Option 10 | Option 14 |
|--|-----------|------------------|
| Meets ERCOT and NERC Reliability Criteria | Yes | Yes |
| Improves Long-Term Load Serving Capability | Yes | Yes (Best) |
| Improves Operational Flexibility | Yes | Yes (Marginally) |
| Additional transfer circuits from Southern Texas | 2 | 1 |
| Requires CCN* (miles) | ~87 | ~58 |
| Project Feasibility | Yes | Yes |
| Cost Estimate* (\$M) | ~492 | ~435 |

* Cost estimates were provided by Transmission Service Providers (TSPs)

• Final Short-list: Options 10 and 14



Preferred Option

- Option 14 is selected as the preferred option because it
 - Addresses the reliability violation
 - Provides the best combined long-term load serving capability
 - Requires the least mileage of CCN and ROW
 - Is the least expensive option



Sub-Synchronous Resonance (SSR) Assessment

- Sub-Synchronous Resonance (SSR) Assessment was conducted for the preferred Option 14 per Nodal Protocol Section 3.22.1.3
 - ERCOT found no adverse SSR impacts to the existing and planned generation resources at the time of this study



Next Steps and Tentative Timeline

- Tentative timeline
 - EIR Report to be posted in the MIS
 - April 2024
 - EIR recommendation to TAC
 - o April 2024
 - Seek ERCOT Board of Directors endorsement
 - o April 2024





Stakeholder comments also welcomed through:

Caleb.Holland2@ercot.com

Robert.Golen@ercot.com



Appendix A – Transmission Projects Added to Study Case

| TPIT No | Project Name | | Project ISD | TSP | County |
|---------|---|--------|-------------|-------------|---------------|
| 67992 | CPSE_345- kV_Howard_Switching_Station,CPSE_Hamilton_to_MedCtr_U pgrade,CPSE_Medina_to_36th_Street_Upgrade | Tier 3 | 26-Jan | CPS | Bexar |
| 71873 | CPSE_Hill Country Auto# 2 Impedance Upgrade | Tier 3 | 25-Jun | CPS | Bexar |
| 71917 | Upgrade STEC Castroville to Pearson to 138-kV | Tier 2 | 25-May | STEC | Medina |
| 71935 | STEC_71935_HCCastrovI138 | Tier 2 | 25-Feb | STEC | Medina |
| 72882 | LCRATSC_Lockhart_Luling_69kV_TL_Overhaul | Tier 4 | 25-Jun | LCRA TSC | Caldwell |
| 73050 | LCRATSC_JohnDumas_Substation_Addition | Tier 4 | 25-Feb | LCRA TSC | Caldwell |
| 73053 | Wimberley Loop to New Substation | Tier 2 | 27-May | PEC | Hays |
| 73417 | LCRATSC_Schumansville_SheriffsPosse_StormHardening | Tier 4 | 25-May | LCRA TSC | Guadalup e |
| 73793 | LCRATSC_McCartyLaneEast_Zorn_TL_Storm_Hardening | Tier 4 | 25-May | LCRA TSC | Hays |
| 73838 | LCRATSC_Redwood_SanMarcos_TL_Upgrade | Tier 4 | 25-May | LCRA TSC | Hays |
| 75682 | Add Branch between Libra and Elm Creek | | 23-Nov | CPS | Wilson |
| 76790 | Upgrade Pearsall Auto | | 27-May | STEC | Frio |
| 73025 | CPSE_NEW_SHAULA | Tier 4 | 24-Nov | CPS | Dewitt |

ercot 😓

Appendix B – RTP Placeholder Projects Removed from Study Case

| RTP Project ID | Project Name | TSP | County |
|-------------------|---|--------------------------------|---|
| 2023-SC5 | Beck Road 345/138-kV Substation Expansion | CPS | Bexar |
| 2023-SC19 | South to Central Texas 345-kV Double-Circuit Line Additions | AEN, AEP, LCRA, ONCOR | San Patricio, Bee, Karnes, Wilson, Guadalupe, Comal, Hays, Travis, Williamson |
| 2023-SC10 | Wiseman 138-kV Substation Addition and CPS Multiple Cap Bank Additions | CPS | Bexar, Comal |



Appendix C – Generation Added to Study Case

| GINR | Project Name | Fuel | Project COD | Capacity (MW) | County |
|-----------|----------------------------------|------|-------------|---------------|-----------|
| 22INR0366 | BRP Libra BESS | OTH | 01/26/2024 | 206.21 | Guadalupe |
| 22INR0368 | Padua Grid BESS | OTH | 12/01/2024 | 51.39 | Bexar |
| 22INR0422 | Ferdinand Grid BESS | OTH | 05/31/2026 | 202.65 | Bexar |
| 23INR0027 | Cachena Solar SLF | SOL | 12/31/2025 | 600 | Wilson |
| 23INR0154 | Ebony Energy Storage | OTH | 04/01/2024 | 203.5 | Comal |
| 23INR0381 | Soportar ESS | OTH | 03/15/2025 | 102.11 | Bexar |
| 24INR0427 | CPS AvR CT1 Rotor Replacement | GAS | 01/30/2024 | 11.3 | Bexar |
| 25INR0223 | Uhland Maxwell | GAS | 04/15/2025 | 181.1 | Caldwell |
| 22INR0251 | Shaula I Solar | SOL | 10/30/2025 | 205.2 | DeWitt |
| 22INR0267 | Shaula II Solar | SOL | 05/30/2026 | 205.2 | DeWitt |



Appendix D – G-1 Generators and X-1 Transformers

| G-1 Generators | X-1 Transformers |
|---|------------------------------------|
| Guadalupe – GUADG_GAS1 GUADG_GAS2 GUADG_STM5 | Hill Country – Ckt 1 345/138-kV |
| San Miguel – SAN_SANMIGG1 | Marion – Ckt 1 345/138-kV |
| Spruce – CALAVER_JKS2 | San Miguel – Ckt 1 345/138-kV |
| | Skyline – Ckt 1 345/138-kV |

